

# ROAD STUD INSTALLATION UNIT

## TECHNICAL INFORMATION

### ROAD STUD INSTALLATION UNIT

The Somerford Stud Drill machine incorporates a tried and tested hydraulically operated, PTO driven stud drilling unit. Support legs to each corner of the vehicle ensure stability whilst working. A single 175 litre vertical preheater for preheating of bituminous compound is mounted to the rear lowered platform. Operator controls are mounted inboard of the body, complete with operator seat. Vehicles are fitted with warning lights and rear sign board for traffic control.

### OPTIONS

- Powerful suction system for debris removal
- Flexible hose with rigid nozzle for ease of handling and proficient suction operation from milled holes
- Waste storage area with tapered base for efficient tipping
- 275 vertical preheater litre capacity upgrade
- Bucket heater mounted to rear lowered platform
- Hand tools and drying equipment compressor
- Fully electronic rear arrow display system

### OUR RANGE OF CUTTING TOOLS

Somerford Equipment offer a range of standard cutting head fitted tools:

- Designed to give the contractor ultimate accuracy and longevity
- Constantly field tested and monitored on all types of road surfaces
- Manufactured for maximum wear resistance
- Temperature controlled electronically when tempering back for ultimate tough performance without breakage
- Designed for an arduous industry where cost and performance are at the forefront
- Available for hole boring diameters from 100mm to 160mm
- Available in standard and T-Style from stock for same-day collection or next day delivery
- L-Style tools can be supplied to order
- Made to order for specific specialist hole stud applications

In addition to the supply of cutting tools, we can carry out cutting head upgrades to your equipment, giving the ability to accept the six-tool head profile. We also offer a cutting tool refurbishment and regrind service.